



**GOVERNMENT COLLEGE OF ENGINEERING,  
CHHATRAPATI SAMBHAJINAGAR**

(An Autonomous Institute of Govt. of Maharashtra) Railway  
Station Road, Osmanpura, Chhatrapati Sambhajinagar.  
"In Pursuit of Technical Excellence"



☐-office:(0240)2366101, 2366102,366111  
e-mail-office.gcocaurangabad@dtmaharashtra.gov.in

web:www.geca.ac.in

GECA/BW/CED/2024/349

Date: 18 JAN 2025

To,  
Notice Board  
College Web site

Subject: Quotation for repair of kerb wall in institute campus at Govt College of Engineering, Chh Sambhajinagar (Due date 07/1/2025)

Dear Sir,

You are requested to send your competitive quotations for the supply of the following items subject to the following conditions:

**CONDITIONS:**

- Rates quoted should be for AURANGABAD or free delivery at the institution.
- Detailed specifications of the articles you intend to supply should be given, if not according to the specification, laid down hereunder.
- S.T or CST should be shown extra if any.
- The work is to be completed with in 8 days after receiving work order. List of works to be executed is attached as below.
- The earliest delivery period should be quoted if you cannot supply within the period mentioned above.
- Quotation should be in sealed covers & superscribed as "QUOTATION FOR----- DUE NO----
- Quotation should be valid for 3 months.
- Quotations not complying with the above conditions and incomplete once will not be considered.
- Right to reject any or all quotations rates with the undersigned.
- No advance payment/part payment shall be made.
- Supplier should submit GST as well as PAN no with the quotations.
- Contractor must be registered with PWD.

Sr No	Name of the material with specification	Approx Quantity
1	Providing second class Burnt Brick masonry with conventional/I.S.type brick sin cement mortar1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc Complete.	35 cu m
2	Providing internal cement plaster 6mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete surface in all positions including scaffolding and curing etc. complete. 1900 sq m	1900 sq m
3	Providing and applying white-wash in one coat on old/new plastered or masonry surfaces and asbestos cement sheets including scaffolding and preparing the surface by brushing and brooming down etc. complete. 2200 sq m	2200 sq m
4	Providing and applying colour-wash of approved colour and shade in two coats to new surface including scaffolding, brushing and brooming down complete. 2200 sq m	2200 sq m
5	Providing neeru finish to plastered surfaces in all positions including scaffolding and curing etc. complete. 1900 sq m	1900 sq m

Yours Faithfully,

Principal