



**GOVERNMENT COLLEGE OF ENGINEERING,
CHHATRAPATISAMBAHAJINAGAR**

(An Autonomous Institute of Govt. of Maharashtra)
Railway Station Road, Osmanpura, Chhatrapati Sambhajinagar.

"In Pursuit of Technical Excellence"

☎-office:(0240)2366101, 2366102,366111

e-mail-office.geceaurangabad@dtmaharashtra.gov.in

web:www.geca.ac.in



GECA/BW/CED/2025/ 4263

Date:

25 NOV 2025

QUOTATION Inquiry

To,

- ✓ 1. Institute Website
2. Notice Board
3. Institute copy

Sub:- Quotation for providing false ceiling in TOM lab of Mechanical Engineering Department at Govt. College of Engineering, Chh Sambhajinagar

Sir,


You are requested to send your quotations on following conditions in sealed envelope for the supply of the item listed herewith mention letter no & date of opening on the quotations on the envelope. Submit the same on or before Date: - 1 / 12 /2025 up to 05.p.m.

TERMS AND CONDITIONS:

1. EMD of 1% of the tender amount will be deposited either in the form of bank guarantee or fixed deposit.
2. Taxes to be paid extra. It will be your responsibility to deposit GST to government.
3. After satisfactory completion of the work as per specifications and testing, the payment will be released.
4. No advance payment will be made.
5. The rates are valid for 6 months from the date of order/till the satisfactory completion of the work.
6. Either party shall have the right at any time by giving notice in writing to the other party to terminate the Contract with immediate effect.
7. To furnish the materials described in this Purchase Order Contract within the time or times specified there for and at the price indicated, and to deliver same where required free and clear of any lien, lien right, royalties, or extra charges of whatever nature, including taxes of any description not shown on the Purchase Order Contract.
8. Full payment shall not be construed as acceptance of defective workmanship or improper materials.
9. That materials furnished comply with all provisions of applicable plans and specifications; that no materials are furnished which may involve a patent infringement action or claim, and that all materials shall be subject to the guarantee provisions of the specifications.
10. That any change, modification, increase or decrease in the Work or quantities as covered in this Purchase Order Contract or in the plans and specifications in connection therewith shall be in writing and approved by you.
11. The time period for this work is 1 months.
12. PWD Registration is mandatory to all bidders. Attach the PWD registration certificate, PAN card and GST certificate with the quotation otherwise the quotation is liable to be rejected.
13. Workers insurance and safety of them will be on account of bidders.
14. The rates to be quoted percentage above or below the estimated rates.
15. Institute reserves the right to reject any or all the quotations without mentioning the reason.

Details of work are as follows:-

Sr no	Description of item	no	Quantity	Unit	SSR Rate	Amount
1	Providing and fixing false ceiling with eco-friendly light-weight calcium silicate tiles of spint one surface texture aerolite make or equivalent of size 595mm x 595 mm having 15mm thick densified micro look edge and 100% humidity resistance in combustibile as per BS46 part IV and thermal conductivity 0.043w/m 0K C and NRC 0.50 place din true horizontal level suspended grid of size 600 x 600 mm made from hot dipped G.I. steel sections ion silhouette profile, rotary stitched double web bed white with 6mm reveal profile (white/black), where in, main Trunner of size 42mm x 14 mm between main tee 600 mm center-to center and secondary cross To f size33 x 14 x 0.43 mm thick of length 600 mm long spaced inter-locked at middle of the first crossed T in each panel to form grid of 1200mm x 600 mm resting on periphery wall Profile wall section 19mm (7+7) x 19mm x 0.40 thicknesses and laying false ceiling for services like diffusers grills including cutting, making opening for light fittings, fixtures, , smoke detectors etc., wherever required. Main Trunners suspended from ceiling with using G.I. soffit cleats of size 25 x35x1.6 mm of required length fixed to the ceiling with 6mm dia and 50mm long dash fastener, 4mmdia G.I. adjustable rods with powder coated/good quality G.I. level adjustment clips of 35x35x0.8mm spaced@1200, center-to-center along main Tall complete at all heights as per the specifications, drawings	1	56	Sqr.m	₹ 2,045.00	₹ 114,520.00
Total Estimated Amount						₹ 114,520.00


(Dr. S. S. Damhare)
Principal